Taneytown, MD

Phone: +14107562430
115 York St
Taneytown, Maryland
Email: adam@hitchman.com



7 x 12 Sure-Trac Scissor Hoist HD Dump Trailer, 12k GVWR w/Tarp Kit & 110V Battery Charger

Type	Trailer or Truck Bed	**Category**	Dump Trailer
Stock#	T8869	**Location**	Taneytown, MD
Year	2027	**Status**	Sold
Condition	New	**Manufacturer**	Sure-Trac
Model	7 x 12 12k Scissor Hoist	**Floor Length**	144in / 12ft
Floor Width	84in / 7ft	**GVWR**	12000
Weight	3240	**Payload Capacity**	8760
Axle Capacity	12000		
Color	Black	**Pull Type**	Bumper
Axles	2	**Suspension Type**	Leaf Spring Suspension
Construction	Steel	**Side Wall Height**	24in / 2ft

https://thehitchmaninc.com/unit/7-x-12-sure-trac-scissor-hoist-hd-dump-trailer-12k-gvwr-w-tarp-kit-110v-battery-charger-1021115

Call for Price

Description

82 IN x 12 HD Low Profile Dump Trailer, 12K Scissor
GVWR (lbs)
12000
GAWR (lbs/axle)
6000
Curb Weight
3735
Payload
8265
Width
7
Length
12
Overall Length
198
Deck Length
144
Deck Width
82
Deck Height
29
Coupler Height
19-27
Height Interior
24
Width Interior
82
Type
OPEN
110V Electrical
On-Board Charger 4 Amp (110V Plug In)
12V Electrical
12 Volt DC 24 Battery
Axle
(2) 6000 lb. Slipper Spring Brake
Breakaway
Battery, Switch, and Lanyard
Connector Plug
Round 7-pin Blade
Coupler
2-5/16" Adjustable
Crossmembers
4" Steel Channel
Decking
10-Gauge Smooth Steel
Exterior Finish
Industrial Grade Polymer Finish
Exterior Lights

Full LED, DOT Compliant
Exterior Storage
Drop-In (Recessed) Lockable Battery and Pump Box, Spare Tire Carrier, Underbody Secure Tool Storage
Fenders
Double Break Tread Plate
Frame
5" x 2" Steel Tube
Hubs
Easy Lube
Hydraulic Components
12 Volt Hydraulic Pump, Power Up, Gravity Down (Scissor Lift Hoist)
Integrated Step(s)
Side Steps
Ramp(s)
3" x 80' Steel Ladder Style (Slide-In with Carrier)
Safety Chains
DOT Compliant
Sides
Board Holders, Integrated Side Body Stiffening System
Stabilizers
Stabilizer Jack Receivers (Jacks Optional)
Tarp
18' Mesh Tarp Kit (Installed), Anti-Sail Kit with Integrated Tie-Down, Integrated Tarp Mount and Shroud
Tie Downs
(5) 1/2" D-Rings, Stake Pockets
Tires
ST235/80R16E 10-PR
Tongue
5" x 2" Steel Tube
Tongue Jack
7K Drop Leg, Set-Back
Top Rail
2" x 2" Steel Tube
Wheels
16", 8-Hole Steel
