Ken Feagin Truck & Trailer

Phone: +18645108832
4125 Compton Bridge Rd
Campobello, South Carolina
Email: monica.kftt@gmail.com



2027 Hawke Trailers 7 X 14 17K Low Profile Dump Trailer

Type	Trailer or Truck Bed	**Category**	Dump Trailer
Stock#	HK7X14SD17k	**Location**	Ken Feagin Truck & Trailer
Year	2027	**Status**	Available
Condition	New	**Manufacturer**	Hawke Trailers
Model	7 X 14 17K Low Profile	**Floor Length**	168in / 14ft
Floor Width	84in / 7ft	**GVWR**	17000
Weight	4200	**Payload Capacity**	12800
Axle Capacity	8000		
Pull Type	Bumper	**Axles**	2
Clearance Price	12480	**Construction**	Steel

Side Wall Height	24in / 2ft		

https://kenfeagintruckandtrailer.com/unit/2027-hawke-trailers-7-x-14-17k-low-profile-dump-trailer-1051776

Price: $0.00

Sales Price: $12,480.00

Description

Payload Capacity: *12,800 lbs*

- Super duty scissor hoist
- 5? x 20? hydraulic cylinder (power up / power down)
- (2) 8,000 lb Dexter braking axles
- 2-way tailgate with combination barn door/spreader gate
- Tarp system with aluminum pull bar
- Large, Lockable, Tongue Mounted toolbox with divider
- (4) D-rings inside dump box
- Stake Pockets
- Deep cycle battery
- Spare tire mount
- Rear drop-leg stabilizer jack
- US-made hydraulic pump
- 20? wired hand remote
- Slipper spring suspension
- 215/75 R17.5 Load Range J (18 ply) Westlake radial tires
- 8? channel main frame & tongue
- 3x3 tubing dump box frame
- 3? channel crossmembers on 16? centers
- 3/16? steel floor
- 12-gauge steel walls
- 30? headboard with 24? sides
- Raised rear corner posts with lumber gussets (for side extensions)
- 80? heavy-duty slide-in ramps, 4? channel construction & 12,000 lb capacity
- 2-5/16? adjustable cast coupler (5-position track)
- 12,000 lb drop-leg jack
- Phosphate washed
- Epoxy primer base
- Dual-stage polyurethane paint finish
- Sealed US-made wiring harness
- LED lighting
- DOT-approved safety chains
- Breakaway system
- DOT reflective tape
- Inside Width: 83?

"Crafted with Pride" in Marietta, SC for over 26 years.
