Trailer Ranch SC

Phone: +18037472793
1370 Five Chop Rd
Orangeburg, South Carolina
Email: meta@trailerranchsc.com

2026 Hawke Trailers 7X14 14K Dump Trailer

Type	Trailer or Truck Bed	**Category**	Dump Trailer
Stock#	02060	**VIN**	7PWFL1424TM002060
Location	Trailer Ranch SC	**Year**	2026
Status	Sold	**Condition**	New
Manufacturer	Hawke Trailers	**Model**	7X14 14K
GVWR	14000	**Weight**	3700
Payload Capacity	10300		
Color	Black	**Axles**	2
Clearance Price	8299	**Msrp**	12259
Construction	Steel		

https://www.trailerranchsc.com/unit/2026-hawke-trailers-7x14-14k-dump-trailer-1157657

Price: $8,299.00

MSRP: $12,259.00
Sales Price: $8,299.00

Description

GVWR: 14,000 lb.
Capacity: 10,300 lb.
Running Gear
7,000 lb. Dexter Brand Braking Axles with Slipper Spring Suspension
235/80 R16 Load Range E 10 Ply Westlake Radial Tires
Frame/Dimensions
8? Channel Main Frame – 6? Channel Tongue
3×3 Tubing Dump Box Frame
3? Channel Crossmembers on 16? Centers
10 Gauge Floor & 12 Gauge Wall
30? Headboard With 24? Sides, Raised Rear Corner Post with Lumber Gussets (Allows You to Extend Your Wall Height)
83? Inside Width
Hydraulics
US Made Pump With 20? Hand Remote, (Optional Wireless Remote) Deep Cycle Battery
Scissor Hoist (Power Up Power Down)
Ramps
80? Long – HD 4? Channel Easy Access Slide-In Loading Ramps. Capacity #12,000
Tailgate
Two Way Tailgate Opens for Dumping Bulk Materials or Can Be Set in Spreader Mode
Coupler
2 5/16? Adjustable Coupler On 5 Position Track
Jack
12,000 Ib. Drop Leg Jack
Electrical/Safety
Sealed US Made Wiring Harness with LED Lighting
DOT Approved Safety Chains, Break-a-Way Switch and DOT Tape
Paint
Phosphate Washed, Primed with Epoxy Primer and Two Coats of Polyurethane Paint
Standard Features
Lockable Toolbox with Tool Divider
(4) D-Rings mounted to Wall on Inside of Dump Box
Tarp System With Aluminum Pull Bar
Spare Tire Mount
Lenders available for financing
Trailer Ranch
1370 Five Chop Road
Orangeburg SC 29115
803-747-2793
www.trailerranchsc.com