Newbury

Phone: +14405641234
14555 Ravenna Rd
Newbury, Ohio
Email: paul@oreillyequipment.com



2027 Sure-Trac 6' 6" x 12' Gravity Tilt Trailer - 7800# GVW

Type	Trailer or Truck Bed	**Category**	Tilt Trailer
Stock#	498674	**VIN**	5JW2U1711V1498674
Location	Newbury	**Year**	2027
Status	Available	**Condition**	New
Manufacturer	Sure-Trac	**Model**	ST-TSA7812-078
Floor Length	144in / 12ft	**Floor Width**	78in / 6ft 6in
GVWR	7800	**Weight**	1900
Payload Capacity	5900		
Color	Black	**Width Total**	78"
Wheels	Silver	**Pull Type**	Bumper
Axles	1	**Suspension Type**	Torsion Suspension
Construction	Steel		

https://oreillyequipment.com/unit/2027-sure-trac-6-6-x-12-gravity-tilt-trailer-7800-gvw-1215083

Price: $6,200.00

Description

SURE-TRAC - SINGLE AXLE GRAVITY TILT BED EQUIPMENT TRAILER
STANDARD SPECS/FEATURES:

- FRAME: 5 x 2 Tube
- CROSS MEMBERS: C-Channel 16" On Center
- TONGUE: 5 x 2 Tube
- COUPLER: Adjustable 2-5/16" Ball Coupler
- JACK: Setback 7k Drop Leg
- FENDERS: HD Tread Plate
- AXLES: Torsion Axle With Easy Lube Hubs And Brakes
- TIRES/WHEELS: 225/75R15 LRD - 15" 6 On 5.5 Radial (6k Trailer)
- TIRES/WHEELS: 235/80R16 LRE - 16" 8 On 6.5 Radial (7.8k Trailer)
- TIRES/WHEELS: 215/75R17.5 LRH - 17.5" On 6.5 Radial (10k Trailer)
- DECKING: 2 x 6 Treated Pine
- LIGHTS: All LED Lights
- ELECTRIC PLUG: 7-Way RV-Style Molded Plug
- FINISH: Powder Coated High Gloss Black
- BETWEEN FENDERS: 62" (6K Trailer)
- BETWEEN FENDERS: 78" (7.8k & 10k Trailer)
- DECK HEIGHT: 17" (6k Trailer)
- DECK HEIGHT: 19" (7.8k Trailer)
- DECK HEIGHT: 21" (10k Trailer)

OTHER STANDARD FEATURES:

- Rear Board Retainer
- Stake Pockets and Rub Rail
- 11.5 Degree Tilt Angle
- (4) 5k D Ring Tie Downs
- Spare Tire Carrier
- HD Diamond Plate Tapered Entry Ramp
- C-Channel Full Wrap Tongue
- 4' Front Stationary Deck

OPTIONS ON THIS UNIT:

- Spare Tire Carrier
