Mableton

Phone: +16783413550
1375 Veterans Memorial Highway SE
Mableton, Georgia
Email: salesatl@countryboy-trailers.com



2027 Diamond C 82x14' Dump, 44" Sides, 7 Gauge, 3-Way Gate, Ramps LPT207

Type	Trailer or Truck Bed	**Category**	Dump Trailer
Stock#	18557 M LPT207	**VIN**	46UDD1424V1318557
Location	Mableton	**Year**	2027
Status	Sold	**Condition**	New
Manufacturer	Diamond C Trailers	**Model**	LPT207
Floor Length	168in / 14ft	**Floor Width**	82in / 6ft 10in
GVWR	15500	**Weight**	5870
Payload Capacity	9630	**Axle Capacity**	7000
Color	Gray	**Fenders**	3/16" Dia Plate, Super Heavy Duty
Coupler	2-5/16"	**Jack**	2 speed

Pull Type	Bumper	**Axles**	2
Msrp	19995	**Construction**	Steel
Warranty	6 Year	**Brakes**	Elec. Drum
Lights	LED	**Side Wall Height**	44in / 3ft 8in
Floor	Steel	**Hydraulics**	Yes Dump
Beavertail	No	**Gate**	3-Way

https://www.countryboy-trailers.com//unit/2027-diamond-c-82x14-dump-44-sides-7-gauge-3-way-gate-ramps-lpt207-1247400

Price: $18,599.00

MSRP: $19,995.00

Description

Our price is for cash, check or debit card; Please add 3% for credit cards.
82"x14' LPT207
CEMENT GRAY - POWDER COATED
20' HEAVY DUTY BLACK MESH W/LONG ARM TARP SYSTEM
ST235/80R16 RADIAL 14 PLY TIRES, 8 HOLE BLACK
2 EXTRA 5/8" D-RINGS (6 TOTAL)
5 STAGE HYDRAULIC SYSTEM, POWER UP, GRAVITY DOWN
20K HYDRAULIC JACK
STABILIZER JACK, DROP-LEG (PAIR)
STEP - 1 - 24" SIDE STEP - DRIVER SIDE
3/16" FENDERS DIA PLATE, SUPER HEAVY DUTY
BOARD BRACKETS W/BOARDS & RAISED FRONT
44" SIDES, 7GA (3/16") FLOOR & SIDES (L14)
78" REAR SLIDE-IN RAMPS (3" IBEAM)
3-WAY DUMP GATE (STANDARD)
SPAREMOUNT
ENGINEERED TONGUE W/ HD V-TONGUE LID
2-5/16" COUPLER, 21K DEMCO EZ-LATCH (ADJ CHANNEL)
8"X15# I-BEAM FRAME WITH 16" CENTER CROSSMEMBERS
6-LEAF SLIPPER ROLLER SPRINGS SUSPENSION
2 - 7K DROP AXLE, ELECTRIC DRUM BRAKES
6 YEAR WARRANTY!
