Rogersville - Sancrest Sales

Phone: +14178444903
5070 S. Farm Rd. 219
Rogersville, Missouri
Email: ryan@sancrest.com



2027 MAXX-D 96 X 16 D9X TANDEM DECK OVER DUMP W/ 24" FOLD DOWN SIDES/ 7GA FLOOR/ 10GA SIDES/ SLIDE IN RAMPS

Type	Trailer or Truck Bed	**Category**	Dump Trailer
Stock#	147636	**VIN**	5R8BD1624VM147636
Location	Rogersville - Sancrest Sales	**Year**	2027
Status	Available	**Condition**	New
Manufacturer	MAXX-D	**Model**	D9X TANDEM DECK OVER DUMP W/ 24" FOLD DOWN SIDES/ 7GA FLOOR/ 10GA SIDES/ SLIDE IN RAMPS/ 96X16
Floor Length	192in / 16ft	**Floor Width**	96in / 8ft
GVWR	17500	**Weight**	5670
Payload Capacity	11830	**Axle Capacity**	8000
Color	Black	**Pull Type**	Bumper
Axles	2	**Construction**	Steel

https://sancrestsales.com/unit/2027-maxx-d-96-x-16-d9x-tandem-deck-over-dump-w-24-fold-down-sides-7ga-floor-10ga-sides-slide-in-ramps-1257850

Price: $15,900.00

Description

16' X 96" - 14K 96" Deckover Dump
PO Num / Line: / 143264 Rebate $500
G13 - 17,500 LB GVWR
C10 - 2 5/16" DEMCO ADJUSTABLE COUPLER
J04 - 1-10K DROP-LEG JACK
N20 - I-BEAM TONGUE WITH TOOLBOX
F117 - 10" X 12LB I-BEAM FRAME WITH TELESCOPIC CYLINDER
X07 - 3" CHANNEL ON 12" CENTERS
R38 - 24" SPRING ASSISTED HINGED SIDES
D06 - NO DOVETAIL/8' SLIDE-IN RAMPS
A74 - 2-8K DEXTER ELECTRIC BRAKE AXLES
S02 - SLIPPER SPRING SUSPENSION
T29 - SINGLES (4) ST215/75R17.5 18PLY TIRES FOR 2-8K
P14 - NOT APPLICABLE
E13 - 7 GAUGE FLOOR ONLY/10 GAUGE SIDES
L03 - FLUSHMOUNT LED'S / STANDARD SEALED WIRING HARNESS
O01 - WET BLACK & PRIMER
Y05 - SHURCO PULL BACK TARP SYSTEM
Y64 - TUFF WIRELESS REMOTE W/HYD&POWER OPTIONS W/ NOCO BATTERY CHARGERS
D146 - SPLIT/SPREADER GATE STANDARD
Y03 - SPARE MOUNT
