# North Augusta

Phone: +18038443242
5950 Jefferson Davis Highway
North Augusta, South Carolina
Email: geddings@nacustoms.com

---




## 2027 Load Trail 7 X 14 14K Dump Trailer

| | | | |
|---|---|---|---|
| **Type** | Trailer or Truck Bed | **Category** | Dump Trailer |
| **Stock#** | 395083 | **VIN** | 4ZEDT1422V3395083 |
| **Location** | North Augusta | **Year** | 2027 |
| **Status** | Available | **Condition** | New |
| **Manufacturer** | Load Trail | **Model** | DT142 |
| **Floor Length** | 168in / 14ft | **Floor Width** | 83in / 6ft 11in |
| **GVWR** | 14000 | **Weight** | 4269 |
| **Payload Capacity** | 9731 | **Axle Capacity** | 7000 |
| **Color** | Black | **Pull Type** | Bumper |
| **Axles** | 2 | **Suspension Type** | Leaf Spring Suspension |
| **Construction** | Steel | **Side Wall Height** | 24in / 2ft |

https://www.nactrailersales.com//unit/2027-load-trail-7-x-14-14k-dump-trailer-1259369

**Price: $11,995.00**

---

**Description**

83" x 14' Tandem Axle Dump Low-Pro Dump
8" x 13 lb. I-Beam Frame
2 - 7,000 Lb Dexter Spring Axles (2 Elec FSA Brakes)
ST235/80 R16 LRE 10 Ply. (BLACK WHEELS)
Coupler 2-5/16" Adjustable (6 HOLE)
Diamond Plate Fenders (weld-on)
16" Cross-Members
24" Dump Sides w/24" 2 Way Gate (7 Gauge Floor)
REAR Slide-IN Ramps 80" x 16"
Jack Spring Loaded Drop Leg 1-10K
Lights LED (w/Cold Weather Harness)
4 - D-Rings 4" Weld On
Front Tongue Mount (MAX-Box w/Divider)
Telescopic Cylinder
Standard Battery Wall Charger (5 Amp)
Tarp Kit Top Mount
Rear Support Stands (2" x 2" Tubing)
1 - MAX-STEP (20")
Spare Tire Mount (HD)
Black (w/Primer)