# Cumming

Phone: +17708878508
1550 Atlanta Hwy
Cumming, Georgia
Email: sales@countryboy-trailers.com

---



## 2027 Diamond C 8.5x22' Equipment, 18' Tilt, 4' Stationary HXD208

| | | | |
|---|---|---|---|
| **Type** | Trailer or Truck Bed | **Category** | Equipment Trailer |
| **Stock#** | 19830 C HXD208 | **VIN** | 46UDT2227V1319830 |
| **Location** | Cumming | **Year** | 2027 |
| **Status** | Available | **Condition** | New |
| **Manufacturer** | Diamond C Trailers | **Model** | HXD208 |
| **Floor Length** | 264in / 22ft | **Floor Width** | 102in / 8ft 6in |
| **GVWR** | 18000 | **Weight** | 4800 |
| **Payload Capacity** | 13200 | **Axle Capacity** | 8000 |
| **Color** | Black | **Coupler** | 2-5/16 |
| **Pull Type** | Bumper | **Axles** | 2 |
| **Msrp** | 22995 | **Construction** | Steel |
| **Warranty** | 6 year | **Brakes** | Electric Drum with ABS |

https://www.countryboy-trailers.com/unit/2027-diamond-c-8-5x22-equipment-18-tilt-4-stationary-hxd208-1265785

**Price: $18,995.00**

**MSRP:** $22,995.00

---

**Description**

Our Price is for Cash, Check or Debit Card; Please add 3% for Credit Cards.
HXD208
8.5X22 - 18' Tilt, 4' stationary
Max Wide Package
10 ga. H/D drive-over Fenders w/frame ext.
2-5/16 21K Coupler
HD/V-Tongue Box
2-8000lb axles w/electric drum brakes & ABS
6-leaf slipper roller spring suspension
Hydraulically Dampened Tilt
3" Cross members 16" on Center
2" treated floor rub rail w/stake pockets
4 D-Rings
St215/75R17.5 18 ply Tires
Spare mount & tire
15K Drop-Leg Jack 2-Speed
Rub rail with stake pockets & pipe spools
18K GVWR
6 Year Warranty

---