I-35 Trailer Store - Seagoville

Phone: +19722878000
1109 N Highway 175
Seagoville, Texas
Email: service@i35trailerstore.com



2027 Iron Bull DBB 16’x83” Dump Roll Off w/2 Bins

Type	Trailer or Truck Bed	**Category**	Roll Off
Stock#	9544	**Location**	I-35 Trailer Store - Seagoville
Year	2027	**Status**	Available
Condition	New	**Manufacturer**	Iron Bull
Model	DBB 16’x83”	**Floor Length**	192in / 16ft
Floor Width	83in / 6ft 11in	**GVWR**	14999
Weight	3870	**Payload Capacity**	11129
Color	Black	**Side Wall Height**	48in / 4ft

https://i35trailerstore.com/unit/2027-iron-bull-dbb-16-x83-dump-roll-off-w-2-bins-1266002

Price: $20,895.00

Description

2027 Iron Bull DBB 16’x83” Dump Roll Off w/2 Bins
2 - 7,000 Lb Axles Straight .
10" I-Beam Frame
Spare Tire Mt.

Bumper Pull Adj 14k Coupler 2 5/16
Diamond Plate Fenders (Bolt On)
Jack Spring Loaded Drop Leg 1-10K
Front Tool Box w/ Pump
Scissor Hoist TH-520
Lighting LED (OVAL 6")
Standard Wiring Harness
ST235/80 R16 LRE 10 Ply.
Winch With Cable 20,000 LB
Safety Chain On Deck
Side Step Plate
BINS
Tube 2" X 3" Frame
48"-10GA Dump Sides Std
1/4" Stacking Brackets
4 1/2" Diameter Front & Rear Rollers With Grease
Double Rear Swing Out Doors
Tarp System (Front Mount)
7" Stake Pocket
D-Rings 3" X 5/8" Weld On (4ech) Std.
