Orlando FL

Phone: +13528013777
2359 US Highway 27/441
Fruitland Park, Florida
Email: jason@iwtrailers.com



2027 Diamond C MDT206 TELESCOPIC Dump Trailer PACESETTER 12K JACKS SOLAR CHARGER

Type	Trailer or Truck Bed	**Category**	Dump Trailer
Stock#	MDT2069923	**VIN**	46UDD1224V1319923
Location	Orlando FL	**Year**	2027
Status	Sold	**Condition**	New
Manufacturer	Diamond C Trailers	**Model**	MDT206
Floor Length	144in / 12ft	**Floor Width**	77in / 6ft 5in
GVWR	9890	**Weight**	3410
Payload Capacity	6480	**Axle Capacity**	6000
Pull Type	Bumper	**Axles**	2
Side Wall Height	24in / 2ft	**Monthly Payment**	185

https://iwtrailers.com/unit/2027-diamond-c-mdt206-telescopic-dump-trailer-pacesetter-12k-jacks-solar-charger-1273879

Price: $11,649.00

Monthly Payment: $185.00

Description

Payments as low as $185 per month with no money down through Diamond C financing with approved credit

MDT206 MEDIUM DUTY DUMP TRAILER - PACESETTER EDITION SOLAR CHARGER

9890 LBS - 206 PKG
FRAME SIZE, L12X77
AXLE, 2 - 6K STRAIGHT 2 ELECTRIC BRAKES
SUSPENSION, 5-LEAF SLIPPER SPRINGS
JACK, 12K DROP-LEG JACK
THREE STAGE TELESCOPIC CYLINDER
HYDRAULIC SYSTEM, POWER UP, GRAVITY DOWN
CROSS MEMBERS, 3" I-BEAM ON 16" CENTERS
DUMP BODY FRAME, 3" X 2" 11GA RECTANGLE TUBE
COUPLER, 2-5/16", 21K DEMCO EZ-LATCH (ADJ CHANNEL)
TONGUE/FRAME, 6" X 8.5 LB I-BEAM
STORAGE, STEEL HYDRAULIC PUMP BOX
SPAREMOUNT - PASSENGER (CURB) SIDE
GATE, 3-WAY DUMP GATE (STANDARD)
RAMPS, 60" REAR SLIDE-IN (2" SQUARE TUBE)
SIDES, 24" TALL, 10GA INTEGRAL W/ FLOOR (L12)
BOARD BRACKETS W/BOARDS & RAISED FRONT
FENDER, 14 GA TEARDROP, DIAMOND PLATE, WELD-ON
STABILIZER JACK, DROP-LEG (PAIR)
BATTERY - GROUP 27
SOLARPULSE CHARGING SYSTEM 7 WATT
TIE DOWN, STANDARD 1/2" D-RINGS (4 TOTAL)
TIRES, ST225/75R15 RADIAL 6 HOLE BLACK
SPARE, ST225/75R15 RADIAL 6 HOLE BLACK
PAINT, ONYX BLACK
LIGHTS, ALL LED
TARP, 18' HEAVY DUTY, BLACK MESH (INSTALLED)
DECALS, MDT
