

Jim Campen Trailer Sales - Arden

Phone: +18286844284
14 Airport Rd
Arden, North Carolina
Email: scott@jimcampen.com



2027 Hillcrest Trailers 176716SDH Dump Trailer / 7' WIDE X 16' LONG / 40" HIGH SIDES / TELESCOPIC HOIST / COMBO REAR GATES / SLIDE OUT RAMPS / 215/75R17.5 16 PLY TIRES / HYDRAULIC JACK

Type	Trailer or Truck Bed	Category	Dump Trailer
Stock#	1749	VIN	7X8BD1628VS001749
Location	Jim Campen Trailer Sales - Arden	Year	2027
Status	Available	Condition	New
Manufacturer	Hillcrest Trailers	Model	176716SDH
Floor Length	192in / 16ft	Floor Width	83in / 6ft 11in
GVWR	17600	Weight	5482
Payload Capacity	12118	Axle Capacity	8000
Color	Gray	Pull Type	Bumper

Axles	2	Suspension Type	Leaf Spring Suspension
Construction	Steel	Side Wall Height	40in / 3ft 4in

<https://jimcampen.com/unit/2027-hillcrest-trailers-176716sdh-dump-trailer-7-wide-x-16-long-40-high-sides-telescopic-hoist-combo-rear-gates-slide-out-ramps-215-75r17-5-16-ply-tires-hydraulic-jack-1294890>

Price: \$15,995.00

Description

Jim Campen Trailer Sales Inc
14 Airport Rd
Arden, NC 28704
Monday - Friday 9-5
Saturday 9-2

828-684-4284 ext 7

828-778-8884 for Scott Campen
828-707-3524 for Cameron Campen

Financing is available!!
Rent to own is available!!
2027 HILLCREST 7X16 DUMP TRAILER
40" HIGH SIDES
TRUE 8 K ELECTRIC BRAKE AXLES
COMBO REAR GATE
MATCHING SPARE TIRE AND WHEEL
215/75R17.5" TIRES AND WHEEL
SLIDE IN RAMPS
TARP SYSTEM
TELESCOPIC HOIST
HYDRAULIC JACK
17600 GVWR
REAR DROP STABILIZER STAMDS
GRAY POWDERCOAT FINISH
3 YEAR STRUCTURE WARRANTY
1 YEAR COMPONENT WARRANTY
Axles (17.6K) 2 - 8000# Premium, Cambered Axles with Oil Bath Hubs Brakes Forward Self-Adjusting Electric Brakes on Both Axles
Suspension Multi-Leaf Slipper Spring w/ Equalizer Tongue
Coupler (17.6K) 2-5/16" Adjustable Demco Coupler
Safety Chains 3/8" Grade 70 w/ Safety Latch Hook (2 ea)
Jack HYDRAULIC
Frame 8" I-Beam, 13LB

Cross-Members 3" Channel on 12" Centers

Floor 7 Ga

Fenders Double Broke

Ramps 6.5' Heavy Duty Ramps

Stake Pockets Stake Pockets Along Both Sides Trailer

Plug 7-Way RV

Wiring Sealed Modular Wiring Harness

Tires (17.6K) ST215/75R17.5 LRJ Tire 16 Ply) - 8 Lug

Tie-Downs (6) 5/8" D-Rings Inside Bed to Secure Equipment Along Sides and Rear for Cargo Control.

Gate Rear Combo Gate (Barn Doors & Spreader Gate)

J-Hooks Along sides for Cargo Control

Electric / Hydraulic Power Up/Gravity Down Movement

Ram 12-Ton 3- Stage Telescopic Cylinder

Stabilizers Rear Stabilizer Stands

Steps Convenient Side-Step for Easy Access

Storage Lockable Pump and Battery Box mounted in Front of Bed

Tarp Fully-Formed Tarp Shroud with Tarp & Rear Tarp Rod Holders

Top Rail Formed Strong Rail
