Rogersville - Sancrest Sales

Phone: +14178444903
5070 S. Farm Rd. 219
Rogersville, Missouri
Email: ryan@sancrest.com



2027 MAXX-D 83 x 16 DTX TANDEM TELESCOPIC GN DUMP W/ 2' SIDES/ 7GA FLOOR/ 10GA SIDES/ SLIDE IN RAMPS

Type	Trailer or Truck Bed	**Category**	Dump Trailer
Stock#	150297	**VIN**	5R8GD1624VM150297
Location	Rogersville - Sancrest Sales	**Year**	2027
Status	Available	**Condition**	New
Manufacturer	MAXX-D	**Model**	DTX TANDEM TELESCOPIC GN DUMP W/ 2' SIDES/ 7GA FLOOR/ 10GA SIDES/ SLIDE IN RAMPS/ 83X16
Floor Length	192in / 16ft	**Floor Width**	83in / 6ft 11in
Color	Black	**Axles**	2
Construction	Steel		

https://sancrestsales.com/unit/2027-maxx-d-83-x-16-dtx-tandem-telescopic-gn-dump-w-2-sides-7ga-floor-10ga-sides-slide-in-ramps-1302193

Price: $16,600.00

Description

18,000 LB GVWR
C17 - 2 5/16" 30K ROUND GN COUPLER
J05 - 2-10K DROP-LEG JACKS ON GN
N74 - STANDARD HEIGHT ENG. NECK W/FRONT TOOLBOX, WINCH PLATE, & SPARE MOUNT
(56" RISER)
F113 - 8" X 15LB I-BEAM FRAME WITH TELESCOPING CYLINDER
X07 - 3" CHANNEL ON 12" CENTERS
R25 - 2' SOLID SIDES ON DUMP TRAILER
D05 - NO DOVETAIL/7' SLIDE-IN RAMPS
A74 - 2-8K DEXTER ELECTRIC BRAKE AXLES
S02 - SLIPPER SPRING SUSPENSION
T29 - SINGLES (5) ST215/75R17.5 18PLY TIRES FOR 2-8K
P06 - DOUBLE BROKE DIAMOND PLATE FENDERS
E13 - 7 GAUGE FLOOR ONLY/10 GAUGE SIDES
L03 - FLUSHMOUNT LED'S / STANDARD SEALED WIRING HARNESS
O01 - WET BLACK & PRIMER
Y05 - SHURCO PULL BACK TARP SYSTEM
Y64 - TUFF WIRELESS REMOTE W/HYD&POWER OPTIONS W/ NOCO BATTERY CHARGERS
D146 - SPLIT/SPREADER GATE STANDARD
J28 - REAR SUPPORT STANDS
Y65 - SPARE TIRE AND MOUNT
Y15 - AGM GROUP 31 BATTERY