Ken Feagin Truck & Trailer

Phone: +18645108832
4125 Compton Bridge Rd
Campobello, South Carolina
Email: monica.kftt@gmail.com

2027 Delta Mfg 16' Stock Bumper Pull Horse Trailer

Type	Horse Trailer	**Category**	Horse Trailer
Stock#	D16STOCKBPESS66TALLBO	**Location**	Ken Feagin Truck & Trailer
Year	2027	**Status**	Available
Condition	New	**Manufacturer**	Delta Mfg
Model	16' Stock Bumper Pull	**Floor Length**	192in / 16ft
Floor Width	72in / 6ft	**Floor Height**	78in / 6ft 6in
GVWR	7000	**Weight**	2861
Payload Capacity	4139	**Axle Capacity**	3500
Color	Silver	**Pull Type**	Bumper
Axles	2	**Construction**	Steel

Stalls	2		

https://kenfeagintruckandtrailer.com/unit/2027-delta-mfg-16-stock-bumper-pull-horse-trailer-1302436

Price: $8,480.00

Description

An economical option built with the same quality expected from Delta including baked-on Urethane paint finish.

Features:

- Center Gate - Standard Gate with Spring-Loaded Slam Latch
- Rear Door - Standard Full Swing with 1/2 Slider
- Electric Brakes on One Axle
- Dexter Eye-to-Eye Spring Suspension
- Frame - 2x3 Angle
- Tongue -3" Channel
- Crossmembers - 2x2 Angle on 16" Center
- Side Uprights - 1 x 2 Tubing on 38" Centers (Approx.)
- Roof - 18 Gauge Metal with Bows on 24" Centers
- 2" Pressure Treated Pine Flooring
- 16 Gauge 48" High Embossed Sides
- Escape Door
- Center Gate with Spring-loaded Slam Latch
- Full Swing Rear Door with 1/2 Slider
- Sealed Fender & Rood joints
- Approx. 14" Deck Height
- 48" High Embossed Sides, 16 Gauge