Osgood, IN

Osgood, IN

2026 NXG Truck Bodies XFD XFD-D978434S

Type	Trailer or Truck Bed	**Category**	Truck Bed
Stock#	12629	**VIN**	NXG012629
Location	Osgood, IN	**Year**	2026
Status	Available	**Condition**	New
Manufacturer	NXG Truck Bodies	**Model**	XFD XFD-D978434S
Color	Black		

https://nealmotor.com/unit/2026-nxg-truck-bodies-xfd-xfd-d978434s-1308562

Price: $5,037.00

Description

Component
Description
Model / Body System
NXG Flatbed / Platform Body
Available Lengths
84", 8'6", 9'4", 11'4" standard configurations
XCoat Finish System
Proprietary multi-stage powder coating system delivering industry-leading corrosion resistance and a durable, professional finish
XDeck
Fully recessed 1/8" steel treadplate deck maximizing cargo space while eliminating exposed edges to reduce wear and corrosion
XRack System
Fully integrated headache rack built into the body (not bolt-on), constructed with precision 3" × 4" steel tubing, mandrel bends, and built-in XLights for superior strength, protection, and safety
XLights
Automotive-grade integrated taillights featuring stop, tail, turn, backup, and built-in amber strobe functions for maximum visibility and job-site safety
XHitch System
Frame-integrated towing system with a 30,000 lb gooseneck hitch and 24,500 lb receiver hitch, complete with upright safety chain keepers, pre-wired electrical connections, and an emergency breakaway loop

Frame Rails
4" precision-cut structural channel steel runners for maximum strength and enhanced corrosion resistance
Crossmembers
3" roll-formed steel crossmembers engineered for superior deck support and load capacity
Side Rails
3/8" × 2" formed steel rub rails with integrated stake pockets and tie-down compatibility
Fuel Fill
Angled rear-facing fill neck designed for cab chassis applications to improve fueling ease and reduce splashback
Marker Lighting
DOT-approved LED bullet marker lights for reliable, road-ready visibility
Trailer Light Plug
Automotive-grade 7-way / 4-way 12-volt trailer wiring connection for dependable trailer hookups

---