New Boston (S.E. Michigan)

Phone: +17346542155
38771 Willow Rd.
New Boston, Michigan
Email: billjones@usa-trailer.com



2027 Load Trail 83x14 Contractors Dump Trailer W/ 7Ga Floor

Type	Trailer or Truck Bed	**Category**	Dump Trailer
Stock#	NB97424	**VIN**	4ZEDT1421V3397424
Location	New Boston (S.E. Michigan)	**Year**	2027
Status	Available	**Condition**	New
Manufacturer	Load Trail	**Model**	83x14 Contractors
Floor Length	168in / 14ft	**Floor Width**	83in / 6ft 11in
GVWR	14000	**Weight**	4230
Payload Capacity	9770	**Axle Capacity**	7000
Color	Black	**Pull Type**	Bumper
Axles	2	**Suspension Type**	Leaf Spring Suspension
Construction	Steel	**Side Wall Height**	24in / 2ft

https://www.usa-trailer.com/unit/2027-load-trail-83x14-contractors-dump-trailer-w-7ga-floor-1311014

Price: $11,399.00

Description

83" x 14' Tandem Axle Dump Low-Pro Dump
8" x 13 lb. I-Beam Frame
2 - 7,000 Lb Dexter Spring Axles (2 Elec FSA Brakes)
ST235/80 R16 LRE 10 Ply. (BLACK WHEELS)
Coupler 2-5/16" Adjustable (6 HOLE)
Diamond Plate Fenders (weld-on)
16" Cross-Members
24" Dump Sides w/24" 2 Way Gate (7 Gauge Floor)
REAR Slide-IN Ramps 80" x 16"
Jack Spring Loaded Drop Leg 1-10K
Lights LED (w/Cold Weather Harness)
4 - D-Rings 4" Weld On
Front Tongue Mount (MAX-Box w/Divider)
Scissor Hoist w/6" Cylinder
Standard Battery Wall Charger (5 Amp)
Tarp Kit Front Mount
Rear Support Stands (2" x 2" Tubing)
1 - MAX-STEP (20")
Spare Tire Mount (HD)
Black (w/Primer)
Road Service Program 833-278-3396 for Info.