St. Louis

Phone: +16369809429
404 South Cool Springs Rd
O Fallon, Missouri
Email: info@totaltrailers.com



8.5 x 28 Front Office / Command / Medical Trailer

Type	Trailer or Truck Bed	**Category**	Office Trailer
Stock#	28 Office Command Trailer	**Location**	St. Louis
Year	2027	**Status**	Available
Condition	New	**Manufacturer**	Total Trailer
Model	28' Front Office Mobile Command Trailer	**Floor Length**	336in / 28ft
Floor Width	102in / 8ft 6in	**GVWR**	13200
Weight	7236	**Payload Capacity**	5964
Axle Capacity	6000		
Color	White	**Width Total**	102
Wheels	Aluminum	**Coupler**	2 5/16
Jack	Manual	**Pull Type**	Bumper
Axles	2	**Nose Type**	Flat
Roof Type	Flat	**Construction**	Aluminum
Brakes	Electric	**Height**	84in / 7ft
Warranty	3 Yr. Structure, Limited Comprehensive, 1 Yr. Electrical	**Floor**	Coin Rubber

https://totaltrailers.com/unit/8-5-x-28-front-office-command-medical-trailer-630552

Price: $109,900.00

Description

8.5 x 28 Front Office / Command Specialty Trailer

AXLE - 6000# - TORSION - EZ LUBE HUBS - ELECTRIC BRAKES
GROUND CLEARANCE: STANDARD (APPROX. 14.25" - NO LOAD)
AXLE SPACING - SPREAD AXLE
ALL TUBE CONSTRUCTION 28 ft
COUPLER - A-FRAME - 2-5/16" - 21,000#
FLOOR DESIGN - FLAT
FRAME - 8"
JACK - TONGUE - SIDE WIND - DROP LEG - 7000
JACK - STABILIZER - SCISSOR - 24" - 5000#
28' FRONT CONFERENCETIRE/WHEEL - ST235/80R16/LRE - RADIAL ON ALUMINUM
TONGUE - EXTENDED TRIPLE TUBE - 12"
TONGUE COVER - ATP
TRUCK PLUG - 7 WAY - BUMPER PULL
BACKER - AL - 0.125" - WALL
EXTERIOR ALUMINUM THICKNESS - .030
FENDERETTES - AL
GRAVEL GUARD - ATP - 24" - WITH J RAIL
ROOF - ONE PIECE - ALUMINUM
TRIM - VERTICALS - FRONT & TOP RADIUS - STAINLESS STEEL W/ CAST CORNERS - POLISHED
VENT - ROOF - MANUAL - 14" - W/MAXXAIR COVER
VENT - ROOF - 12V
DOOR - REAR RAMP - PREMIUM - CONTINUOUS ALUMINUM HINGE - 2400# RATED MAX LOAD -- 4000#
TRANSITION FLAP - TPO - GRAY COIN - 16"L
INTERIOR HEIGHT - 7.5'
28 ft OPTINSULATION - CEILING - FIBERGLASS BATTEN - R-11
FLOORING - TPO - GRAY COIN
FIRE EXTINGUISHER - 2.5# BC
SMOKE DETECTOR
CO DETECTOR
D-RINGS - 5000# - RECESSED
AIRLINE TRACK - SURFACE MOUNT - WALL
WHEEL BOX - SMOOTH AL
BREAKER BOX - 50 AMP - 120V ONLY - 60 AMP CONVERTER - 12V
FUSE PANEL - INTELI-POWER UNIT
BATTERY - 12V AGM (930 CA, 775 CCA)
SWITCH - POWER CUT-OFF - MANUAL - 12V
POWER INLET - MOTORBASE - 50A - W/ SHORE CORD - 25'
LIGHT - SCENE - LED - HIGH OUTPUT - 12V - NON-RECESSED -

14" X 2.5" - CHROME BEZEL
TRANSFER SWITCH - AUTO - 50A
MICROWAVE - 0.9 CU. FT. - 900W - OVEN
INCLUDES: 20A RECEPT - DEDICATED - 120V
PLUMBIING & LP
WATER PUMP - 3.0 GPM - 12V - W/ WINTERIZING TAP
TANK - WATER - FRESH - 48 GALLON
TANK - WATER - BLACK - 45 GALLON
MONITOR PANEL - 2 TANK, BATTERY, WATER PUMP SWITCH
HEATING & AIR CONDITIONING
A/C PREP - BRACE & WIRE
A/C - 15,000 BTU - BLACK - W/ BLACK THERMOSTAT
A/C EASY START
BACKER - 5" WIDE IN WALLS AND CEILING - PREP FOR
PARTITION WALL
HEATER - WALL MOUNT - 120V - 1500W - 5120 BTU - ELECTRIC
AWNING - 12V WITH WEATHER GUARD - 20' - BLACK - BLACK FADE
VINYL FABRIC
CITY WATER HOOK-UP
COMPARTMENT - EXTERIOR ACCESS - 48"W X 40"H X
18"D - LAMINATE COUNTERTOP
DRY ERASE BOARD - 48"W X 36"H
INSULATION - WALLS - CLOSED CELL - R-13
1" CLOSED CELL FOAM INSULATION INSTALLED OVER TOP OF
WALL CROSS MEMBERS (R-6.5)
(1) LAYER 1" CLOSED CELL FOAM INSULATION BETWEEN WALL
CROSS MEMBERS (R-5.5)
MIRROR - 16"W X 20"H
REFRIGERATOR - 4.4 CU. FT. - 120V ONLY
SOFA - FOLD UP SLEEPER - 6' - BLACK - REMOVABLE
WATER - CITY FILL - BLACK
WATER - GRAVITY FILL
GEN- 7KW CUMMINS ONAN