Northwest Arkansas Trailers

Phone: +14799664388
4636 N College Ave
Fayetteville, Arkansas
Email: nwatrailers@gmail.com



2026 Top Hat Trailers 7x12 DPX 140 w/ 7Gauge Floor Dump Trailer

Type	Trailer or Truck Bed	**Category**	Dump Trailer
Stock#	Top_Hat_DP10-12x_x83_7GA14PLY_TIRES	**Location**	Northwest Arkansas Trailers
Year	2026	**Status**	Available
Condition	New	**Manufacturer**	Top Hat Trailers
Model	7x12 DPX 140 w/ 7Gauge Floor	**Floor Length**	144in / 12ft
Floor Width	84in / 7ft	**GVWR**	14000
Axle Capacity	7000		
Pull Type	Bumper	**Axles**	2
Construction	Steel		

https://www.nwatrailers.com/unit/2026-top-hat-trailers-7x12-dpx-140-w-7gauge-floor-dump-trailer-662637

Call for Price

Description

Standard Equipment

Coupler: 2 5/16" Forged Adjustable 5/Position
Jack: Dual 12000# Drop Leg
Fenders: Heavy Duty Diamond Plate Straight
Floor: 7 GA Sheet Metal
Width: 83" Inside Box
Brake: Electric All Wheel
Break Away Unit w/Charger
DOT Reflective Tape
Primed & Painted
Doors: 2- Way Double Action (Barn Door & Spreader Gate)
Ramp Pockets w/7' Ramps
5/8" D-Rings in Box (4)
Spare Rack
Sealed Flush Mount LED Lights
Wiring Harness
Lockable Battery/Pump Box
Deep Cycle 12V Marine Battery w/110V-5 Amp Charger
Factory Installed Tarp Kit
**

Frame Structure

Frame & Tongue: 8" I-Beam Intergrated
Sides: 24" Tall
Toprail: Rigid 3x2 Rectangular Tubing
Uprights: 24" OC
Dump Body Frame: 8" Channel
Crossmembers: 3" Channel 16" OC
Tarp Bracket & Tie Downs
**

Dump Components

Hoist: Scissor Lift
Power Up/Power Down
Control: Pistol Grip w/10' Cord
Safety Prop
Caulked Seams on Dump Body
**

Options

DPX 140 Options
14PLY Tire upgrade
**17,500 GVWR Upgrade **

- DEXTER 8K Oil Bath axles w/ Valcrum Aluminum Oil Caps
- 17.5 16PLY tires
- Big Hoist upgrade

6000# Axles w/12000# GVWR
Deduct 7' Ramps
3' High Side on 12', 14', 16'
4' High Side on 12', 14', 16'

Gas Engine Powered Pump in Lieu of Electric Pump
Spare ST235/80R/16 LRE on 8-Hole
Hydraulic Jack