

# Knoxville TN

Phone: +18653991276  
7880 Asheville Highway  
Knoxville, Tennessee  
Email: jason@iwtrailers.com



## 2026 Big Tex Trailers 160A Deckover Trailer 102”X24’ 17.5K G..V.W.R.

|                  |                      |               |                   |
|------------------|----------------------|---------------|-------------------|
| Type             | Trailer or Truck Bed | Category      | Deckover Trailer  |
| Stock#           | 16OA24knx            | VIN           | I6VIF2626T6435049 |
| Location         | Knoxville TN         | Year          | 2026              |
| Status           | Available            | Condition     | New               |
| Manufacturer     | Big Tex Trailers     | Model         | 160A              |
| Floor Length     | 288in / 24ft         | Floor Width   | 102in / 8ft 6in   |
| GVWR             | 17500                | Weight        | 4600              |
| Payload Capacity | 12900                | Axle Capacity | 8000              |
| Pull Type        | Bumper               | Axles         | 2                 |
| Clearance Price  | 10295                |               |                   |

<https://iwtrailers.com/unit/2026-big-tex-trailers-160a-deckover-trailer-102-x24-17-5k-g-v-w-r-807130>

Price: \$11,595.00

Sales Price: \$10,295.00

### Description

# 2026 BIG TEX 16OA 102"X 24' DECK OVER TRAILER

Tires ST215/75 R-17.5 Load Range H Trailer Plug 7-Way RV  
Brakes Forward Self-Adjusting Electric Brakes on Both Axles Lights Recessed, Grommet-Mounted L.E.D. Lighting  
Suspension Multi-Leaf Slipper Spring w/ Equalizer Wiring Sealed, Modular Cold-Weather Wiring Harness  
Axles 2 - 8,000# Premium, Cambered Axles with Valcrum Hubs and Swivel Flange Nuts Bolt Pattern 8-Lug  
Coupler 2-5/16" Ball, Adjustable Demco EZ Latch Coupler Spare Mount Spare Tire Mount in Toolbox  
Safety Chains 1/4" Grd. 70 w/Safety  
Latch Hook (2 each) Paint Type Professional Finish w/ Primer Standard  
Jack 12,000# Drop Leg Jack (Top Wind), Bolt-On Paint Color Black  
Frame 8" I-Beam (10#) Rub Rail Rub Rail Along Both  
Cross-Members 3" x 3.5" Channel Break-Away Kit Complete Breakaway System w/ Zip Breakaway Cable  
Front Stop Rail 3/16" Fabricated Front Stop Rail Storage Full Tongue Tool Box with Locking Lid  
Floor Treated Pine Floor Side Rail 5" Channel  
Stake Pockets Stake Pockets Along Both Sides, 24" O.C. (Quantity Varies by Length)

---