Knoxville TN

Phone: +18653991276
7880 Asheville Highway
Knoxville, Tennessee
Email: jason@iwtrailers.com



2026 Diamond C LPT207 14’ Dump Trailer 32’HIGH SIDES, TARP, RAMPS, STABILIZER FEET, 15.4K GVWR

Type	Trailer or Truck Bed	**Category**	Dump Trailer
Stock#	LPT2075011	**VIN**	46UDD1429T1305011
Location	Knoxville TN	**Year**	2026
Status	Sold	**Condition**	New
Manufacturer	Diamond C Trailers	**Model**	LPT207
Floor Length	168in / 14ft	**Floor Width**	82in / 6ft 10in
GVWR	15400	**Weight**	5170
Payload Capacity	10230	**Axle Capacity**	7000
Pull Type	Bumper	**Axles**	2

https://iwtrailers.com/unit/2026-diamond-c-lpt207-14-dump-trailer-32-high-sides-tarp-ramps-stabilizer-feet-15-4k-gvwr-874597

Price: $15,195.00

Description

LPT207 LOW PROFILE TELESCOPIC DUMP TRAILER

AXLE, 2 - 7K DROP AXLE, ELECTRIC DRUM BRAKES
SUSPENSION, 6-LEAF SLIPPER ROLLER SPRINGS
FRAME, 8"X15# I-BEAM; 12" CENTER CROSSMEMBERS (L14)
COUPLER, 2-5/16", 21K DEMCO EZ-LATCH (ADJ CHANNEL)
TONGUE, ENGINEERED W/ HD V-TONGUE LID
SPAREMOUNT - PASSENGER (CURB) SIDE
GATE, 3-WAY DUMP GATE (STANDARD)
RAMPS, 72" REAR SLIDE-IN RAMPS (3" CHANNEL)
SIDES, 32" TALL, 10GA INTEGRAL W/ FLOOR (L14)
BOARD BRACKETS W/BOARDS & RAISED FRONT
FENDER, 14 GA TEARDROP, DIAMOND PLATE, WELD-ON
STEP - 1 - 24" SIDE STEP - DRIVER SIDE
STABILIZER JACK, DROP-LEG (PAIR)
JACK, SINGLE 15K SIMOL 2-SPEED DROP-LEG JACK
HYDRAULIC SYSTEM, POWER UP, GRAVITY DOWN
BATTERY - GROUP 27
SOLARPULSE CHARGING SYSTEM 7 WATT
TIE DOWN, STANDARD 5/8" D-RINGS (4 TOTAL)
TIRES, ST235/80R16 RADIAL 14 PLY, 8 HOLE BLACK
SPARE, ST235/80R16 RADIAL 14 PLY, 8 HOLE BLACK
PAINT, ARCTIC WHITE
LIGHTS, ALL LED
TARP, 20' HEAVY DUTY, BLACK MESH W/LONG ARM TARP SYSTEM