US Trailer Center - Shelbyville

Phone: +15024375400
102 Taylorsville Rd
Shelbyville, Kentucky
Email: carolg@ustrailercenter.com



2026 Sure-Trac 7 x 18 (16+2) Equipment 10K Equipment Trailer

Type	Trailer or Truck Bed	**Category**	Equipment Trailer
Stock#	479493	**VIN**	5JW1U2529T1479493
Location	US Trailer Center - Shelbyville	**Year**	2026
Status	Available	**Condition**	New
Manufacturer	Sure-Trac	**Model**	7 x 18 (16+2) Equipment 10K
Floor Length	216in / 18ft	**Floor Width**	82in / 6ft 10in
GVWR	9900	**Weight**	2750
Payload Capacity	7150		
Clearance Price	5975		

https://ustrailercenter.com/unit/2026-sure-trac-7-x-18-16-2-equipment-10k-equipment-trailer-951083

Price: $5,975.00

Sales Price: $5,975.00

Description

Frame : 5" Steel Channel
Crossmembers : 3" Steel Channel, 24" On-Center
Tongue : 5" Steel Channel, Fully Wrapped
Coupler : 2-5/16" A-Frame
Safety Chains : DOT Compliant
Tongue Jack : 7K Drop Leg, Set-Back
Bulkhead : HD Tube
Beavertail : 24"
Ramp(s) : 4" x 5' Spring Assist with Adjustable Support Legs
Fenders : Double Break Tread Plate
Axle : (2) 5200 lb. Spring Brake
Hubs : Easy Lube
Breakaway : Battery, Switch, and Lanyard
Tires : ST225/75R15D 8-PR
Wheels : 15", 6-Hole Steel
Exterior Finish : Industrial Grade Polymer Finish
Decking : 2" Pressure Treated Pine
Tie Downs : (4) 1/2" D-Rings
Tie Downs : Stake Pockets and Rub Rail
Exterior Storage : Spare Tire Carrier
Exterior Storage : Ready for Drop-In (Recessed) Lockable Toolbox
Connector Plug : Round 7-pin Blade
Exterior Lights : Full LED, DOT Compliant
