St. Louis

Phone: +16369809429
404 South Cool Springs Rd
O Fallon, Missouri
Email: info@totaltrailers.com



7 'x 14', 40" Sides, Telescopic, 7ga Floor, 14K (GVWR) Dump Trailer **Tennessee USA Built**

Type	Trailer or Truck Bed	**Category**	Dump Trailer
Stock#	002728	**Location**	St. Louis
Year	2026	**Status**	Available
Condition	New	**Manufacturer**	Hillcrest Trailers
Model	7 'x 14', 40" Sides,Telescopic, 7ga Floor, 14K (GVWR)	**Floor Length**	168in / 14ft
Floor Width	82in / 6ft 10in	**GVWR**	14000
Weight	5132	**Payload Capacity**	8868
Axle Capacity	7000		
Color	Gray	**Pull Type**	Bumper
Axles	2	**Suspension Type**	Leaf Spring Suspension
Construction	Steel	**Length**	168in / 14ft
Width	82in / 6ft 10in		

https://totaltrailers.com/unit/7-x-14-40-sides-telescopic-7ga-floor-14k-gvwr-dump-trailer-tennessee-usa-built-991141

Price: $11,995.00

Description

Hillcrest 7' x 14', 40" Sides, Telescopic, 7ga Floor, 14K (GVWR) Dump Trailer
Axles 2 - 7000# Premium, Cambered Axles with Quick-Lubricating Hubs
Brakes Forward Self-Adjusting Electric Brakes on Both Axles
Suspension Multi-Leaf Slipper Spring w/ Equalizer
Tongue 8" I-Beam, 13LB
Coupler Demco 2-5/16"
Safety Chains 3/8" Grade 70 w/ Safety Latch Hook (2 ea.)
Jack 12,000# Top Wind, Drop Leg, Set-Back Jack
Frame 8" I-Beam, 13LB
Cross-Members 3" Channel on 12" Centers
Floor 7 Ga
Fenders Double Broke
Ramps 6.5' Heavy Duty Ramps
Stake Pockets Stake Pockets Along Both Sides
Trailer Plug 7-Way RV
Wiring Sealed Modular Wiring Harness
Tires ST235/80 R-16 Load Range E Radial Tires- 8 Lug
Tie-Downs (6) 5/8" D-Rings Inside Bed
Gate Rear Combo Gate (Barn Doors & Spreader Gate)
J-Hooks Along sides for Cargo Control
Pump Power Up/Gravity Down Movement
Ram 12-Ton 3 - Stage Telescopic Cylinder
Stabilizers Rear Stabilizer Stands
Steps Convenient Side-Step for Easy Access
Storage Lockable Pump and Battery Box mounted in Front of Bed
Tarp Fully-Formed Tarp Shroud with Tarp & Rear Tarp Rod Holders
Top Rail Formed Strong Rail
Spare ST235/80 R-16 Load Range E Radial Tires- 8 Lug